PANEL-TRIM II

Submittal

High Capacity
Baseboard Radiation

Specification

ENCLOSURE:

STYLE: "Panel-Trim II"

COLOR: White

FRONT: 18-Ga. Roll Formed

Prepainted Galvanized

BACKPLATE: 22-Ga. Roll Formed

Prepainted Galvanized

DAMPER VANE: Roll Formed

Prepainted Galvanized

ELEMENT:

TYPE: Cu/Al Mechanically

Expanded Flared One End

FINS: 2-3/4" x 2-1/2"

FINS/FT: 3/4" - 60

1" - 55

BRACKETS: Die Formed 16-Ga.

Prepainted Steel

SLIDE SHOES: High Temperature

Nylon Snap On

ACCESSORIES: All Overlapping

with Snap On Fit and Powder Coat Finish

3 3/8 (85.7) 1 3/4 (44.4) 1 11/2 (38.1) 2 1/8 (231.8) 4 3/4 (120.6) 1 5/8 (47.6) 1 5/8 (41.3) CAT-55124-A

NOTE: DIMENSIONS IN "()" ARE SHOWN IN MILLIMETERS.

RATINGS

Model	GPM	Average Hot Water Temperature - BTU/Hr./Lin. Ft.								
model		140°F	150°F	160°F	170°F	180°F	190°F	200°F	210°F	220°F
0/4"	4	470	560	650	750	850	940	1040	1140	1240
3/4"	1	445	530	620	710	800	890	980	1080	1170
4"	4	455	540	630	730	820	920	1010	1120	1220
1"	1	430	510	600	690	780	870	960	1060	1150



260 North Elm St., Westfield, MA 01085 (413) 564-5975 Fax: (413) 572-3764

A MESTEK COMPANY

PROJECT:	DATE:
LOCATION:	
ARCHITECT:	
ENGINEER:	
CONTRACTOR:	
PO NUMBER:	

CORRECTION FACTORS

If the calculated water flow rate through a baseboard is greater than the standard flow rate (1 GPM), the rating of that unit may be increased by multiplying the standard water rating at 1 GPM by the factor shown for the actual flow rate. All ratings based on 65°F entering air temperature.

WATER FLOW CORRECTION FACTORS

	Heat Output	Pressure Drop – Millinches Per Ft. Copper Element Tube Size				
G.P.M.	Factor	3/4"	1/2"			
1.0	1.000	47	260			
1.5	1.016	96	520			
2.0	1.028	157	850			
2.5	1.038	230	1270			
3.0	1.045	320	1730			
3.5	1.051	420	2290			
4.0	1.057	525	2880			
4.5	1.062	650	3600			
5.0	1.067	775	4300			
6.0	1.074	1060	5900			

SPECIFICATION

Furnish and install where shown on all plans/drawings, Panel-Trim II Finned Tube Enclosure and Element as described or approved equal of both quality and BTU capacity.

The front panel of the baseboard radiator enclosure, as called out Panel-Trim II, will be manufactured from 18-gauge prepainted galvanized. The backplate will be manufactured from 22-gauge pre-painted galvanized. All lateral bends are to be roll formed to ensure continuity of all adjoining enclosures and accessories. The enclosure lengths are to be provided in 12 inch increments from 2 feet through 8 feet long. The front panel is to be fully engaged onto mounting brackets engaged with the back panel. A panel joiner piece is to be used where two pieces of enclosure are adjoining each other in a run. This is to be supplied in each 5', 6' and 8' assembly package.

All accessories will be die formed 20-gauge cold rolled steel and finished with a powder coat finish. The accessories will overlap the installed enclosure and are to provide adjustment for make-up in the installed runs of enclosure. The accessories will extend to the floor. The accessories are to be enclosure height.

The brackets are to be of a one piece, die formed construction. The material is to be 16-gauge pre-painted bonderized C.R.S. The bracket is to be self locating for vertical positioning at installation. The bottom horizontal leg is to snap into bottom bend of the enclosure and is to support the element where slide shoes are located.

All elements are to be of the mechanically expanded type to ensure that proper fin to tube bonding is maximized. Copper/Aluminum elements are to be provided with one end mechanically swaged (flared) for proper assembly.

In the interest of product improvement, we reserve the right to make changes without notice.