

Performance Data

Without Ductwork

Damper installed per AMCA 500
Fig. 5.5 (Wall Mounted)

Pressure is corrected to .075 lb./cu.ft.
air density

Operational Pressures

Start to Open - .04 inches w.g.
Fully Open - 1.44 inches w.g.



With Ductwork

Damper installed per AMCA 500 Fig.
5.3 (Ductwork installed upstream and
downstream of damper)

Pressure is corrected to .075 lb./cu.ft.
air density

Operational Pressures

Start to Open - .03 inches w.g.
Fully Open - .44 inches w.g.



Typical Performance for Model 335 Backdraft Damper
Size tested 36" x 36", furnished with counterweight to assist opening.