



FLOOR MOUNTING BRACKET

AIR INLET CONNECTION
HIT/MISS DAMPER OPTION
COMM. TUBE
DRIP TRAY

UNIT LENGTH

OVERALL LENGTH

FLOOR MOUNTING BRACKET
DRIP TRAY

SECTION A-A
SCALE 2 1/2"=1'-0"

| AVAILABLE OPTIONS | |
|------------------------------|-------------------------------------|
| Ø 1/2" O.D. SWEAT CONNECTION | <input checked="" type="checkbox"/> |
| Ø 1/2" FEMALE NPT CONNECTION | <input type="checkbox"/> |
| Ø 1/2" MALE NPT CONNECTION | <input type="checkbox"/> |
| AIR INLET SIZE 3" □ 4" □ | <input checked="" type="checkbox"/> |

| NOM. UNIT LENGTH (FT) | UNIT LENGTH (IN) | OVERALL LENGTH (IN) | WEIGHT (LB) |
|-----------------------|------------------|---------------------|-------------|
| 2 | 24 | 28 | 32 |
| 3 | 32 | 36 | 42 |
| 4 | 40 | 44 | 50 |
| 5 | 52 | 56 | 59 |
| 6 | 64 | 68 | 70 |

NOTES:

1. "A" AIR AND COIL HANDINGS SHOWN. REFER TO MODEL CONFIGURATION CHART FOR AVAILABLE OPTIONS.

| | | | |
|---|----|--|---------------------|
| PROJECT SUBMITTAL DRAWING | | | |
| STRICTLY CONFIDENTIAL | | DADANCO - A MESTEK CO. | |
| DADANCO - A MESTEK CO. 47 Westfield Industrial Park Rd WESTFIELD, MA 01085 Ph. (413) 564-5657, Fax. (413) 568-2969 www.dadanco.com | | FLOOR MOUNTED LOW BOY FMLBY SUBMITTAL | |
| DRN | TS | 3/23/2023 | TITLE |
| CKD | SL | 3/23/2023 | |
| APPD | DL | 3/23/2023 | |
| ISSUED | | | PROJECT NO: |
| UNLESS NOTED OTHERWISE ALL DIMENSIONS IN INCHES ANGULAR TOL: 1.0° LINEAR TOL: ±0.02" | | | |
| ANSI STANDARD | | FILE Name: FMLBY_4FT_ECN123_U.iam | |
| | | SCALE: NTS | RELEASE A |
| | | SHEET: 1 / 1 | |