

Input/Output Variables (Read/Write)

Name	SNVT Type/Index	Description	Valid Values/Range												
nviHeatDemand	SNVT_switch 100	Heat Demand/Request. Setting the state member of this variable will put the boiler in heating mode.	<table border="1"> <thead> <tr> <th>state</th> <th>value</th> <th>Interpretation</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>0</td> <td>no heat demand</td> </tr> <tr> <td>0</td> <td>>0</td> <td>heat demand</td> </tr> <tr> <td>1</td> <td>any</td> <td>heat demand</td> </tr> </tbody> </table>	state	value	Interpretation	0	0	no heat demand	0	>0	heat demand	1	any	heat demand
state	value	Interpretation													
0	0	no heat demand													
0	>0	heat demand													
1	any	heat demand													
nviSetpointTimer	SNVT_count 101	<p>System Setpoint Timer</p> <p>The system setpoint timer and system setpoint work in tandem to externally control (i.e. a BMS - building management system) the operating setpoint. The setpoint (countdown) timer should be loaded with a timeout value (in seconds) prior to writing the system setpoint. When the timer reaches zero, the control assumes that the BMS is no longer operating and the local setpoint (saved on the control) is reloaded. This is a failsafe feature used to help safeguard the system in case of BMS failure. If the setpoint timer is not written, a default timeout value of 60 seconds is assumed.</p>	0 – 65535 seconds												
nviSetpoint	SNVT_temp_p 102	System Setpoint (see <i>nviSetpointTimer</i>)	4.5 – 104.4 °C (40 - 220 °F)												
nviOARResetEnable	SNVT_switch 103	Enables/Disables outdoor air reset mode.	<table border="1"> <thead> <tr> <th>state</th> <th>value</th> <th>interpretation</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>0</td> <td>disabled</td> </tr> <tr> <td>0</td> <td>>0</td> <td>enabled</td> </tr> <tr> <td>1</td> <td>any</td> <td>enabled</td> </tr> </tbody> </table>	state	value	interpretation	0	0	disabled	0	>0	enabled	1	any	enabled
state	value	interpretation													
0	0	disabled													
0	>0	enabled													
1	any	enabled													
nviOARSetpoint	SNVT_temp_p 104	Outdoor air reset setpoint. Temperature at which boiler shuts down.	4.5 – 37.8 °C (40 – 100 °F)												
nviOARHiWtrTemp	SNVT_temp_p 105	Boiler water temperature setpoint when outdoor air temperature is at the high outdoor air temperature setpoint (<i>nviOARHiAirTemp</i>).	15.6 – 87.8 °C (60 – 190 °F)												
nviOARHiAirTemp	SNVT_temp_p 106	High outdoor air temperature setpoint.	10 – 32.2 °C (50 – 90 °F)												
nviOARLoWtrTemp	SNVT_temp_p 107	Header/Supply temperature setpoint when outdoor air temperature is at the low outdoor air temperature setpoint (<i>nviOARLoAirTemp</i>).	21.1 – 104.4 °C (70 – 220 °F)												
nviOARLoAirTemp	SNVT_temp_p 108	Low outdoor air temperature setpoint.	-37.2 – 4.4 °C (-35 – 40 °F)												

Name	SNVT Type/Index	Description	Valid Values/Range												
nviSetMonth	SNVT_count 109	Set real time clock – month (<i>see nviSetClock</i>)	0 (January) – 11 (December)												
nviSetDay	SNVT_count 110	Set real time clock – day (<i>see nviSetClock</i>)	1 – 31												
nviSetYear	SNVT_count 111	Set real time clock – year (<i>see nviSetClock</i>)	0 – 99												
nviSetHour	SNVT_count 112	Set real time clock – hour (<i>see nviSetClock</i>)	0 – 23												
nviSetMinute	SNVT_count 113	Set real time clock – minute (<i>see nviSetClock</i>)	0 – 59												
nviSetSecond	SNVT_count 114	Set real time clock – second (<i>see nviSetClock</i>)	0 – 59												
nviSetWeekday	SNVT_count 115	Set real time clock – weekday (<i>see nviSetClock</i>)	1 (Monday) – 7 (Sunday)												
nviSetClock	SNVT_switch 116	Set (write) the real time clock. To write the real time clock, the system variables (nviSetMonth, nviSetMonth, nviSetDay, nviSetYear, nviSetHour, nviSetMinute, nviSetSecond, nviSetWeekday) must first be loaded with the correct date and time. Then, a 1 must be written to the state portion of this system variable to write the new date and time to the system clock.	<table border="1"> <thead> <tr> <th>state</th> <th>value</th> <th>interpretation</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>0</td> <td>---</td> </tr> <tr> <td>0</td> <td>>0</td> <td>set the clock</td> </tr> <tr> <td>1</td> <td>any</td> <td>set the clock</td> </tr> </tbody> </table>	state	value	interpretation	0	0	---	0	>0	set the clock	1	any	set the clock
state	value	interpretation													
0	0	---													
0	>0	set the clock													
1	any	set the clock													
--- The following are supported in bridge configurations 2.30 and greater --- (Control firmware version 2.70 or greater required)															
nviDHWSetpoint	SNVT_temp_p 117	DHW Setpoint Temperature	4.4 – 93.3 °C (40 – 200 °F)												

Input Variables (Read Only)

Name	SNVT Type/Index	Description	Valid Values/Range
nvoBoilersOn	SNVT_count 200	The number of boilers currently running.	0 – 16
nvoModulation	SNVT_lev_cont_f 201	Current system (target) modulation level. This is the modulation level that the system is trying to run at to meet the heating demand.	0 – 100 %
nvoHeaderTemp	SNVT_temp_p 202	Header / System temperature.	0 – 121.1 °C (32 – 250 °F)
nvoSupplyTemp	SNVT_temp_p 203	Supply temperature.	0 – 121.1 °C (32 – 250 °F)
nvoReturnTemp	SNVT_temp_p 204	Return temperature.	0 – 121.1 °C (32 – 250 °F)
nvoOutsideTemp	SNVT_temp_p 205	Outside air temperature.	-40 – 121.1 °C (-40 – 250 °F)
nvoSpare1	SNVT_count 206	Raw A/D value from spare 1 input.	-32768 to 32767
nvoSpare2	SNVT_count 207	Raw A/D value from spare 2 input.	-32768 to 32767
nvoMonth	SNVT_count 208	Real time clock month.	0 (January) – 11 (December)
nvoDay	SNVT_count 209	Real time clock day.	1 – 31
nvoYear	SNVT_count 210	Real time clock year.	0 – 99
nvoHour	SNVT_count 211	Real time clock hour.	0 – 23
nvoMinute	SNVT_count 212	Real time clock minute.	0 – 59
nvoSecond	SNVT_count 213	Real time clock second.	0 – 59
nvoWeekday	SNVT_count 214	Real time clock weekday.	1 (Monday) - 7 (Sunday)

KN2/KN4/rAy LonWorks Bridge Network Variables

v2.30

Name	SNVT Type/Index	Description	Valid Values/Range
nvoClock	SNVT_time_stamp 215	Real time clock date and time.	0 – 11
nvoBlr01Status1 ... nvoBlr16Status1	SNVT_state 300 302 304 ... 328 330 (Even Indices)	Boiler status flags #1. These flags indicate the state of the 24VAC interlocks, ignition circuit, and various other conditions.	See BoilerStatus1 Flags in the Appendix for a list of flags and values.
nvoBlr01Status2 ... nvoBlr16Status2	SNVT_state 301 303 305 ... 329 331 (Odd Indices)	Boiler status flags #2. These flags indicate the state of the ignition circuit, sensors, and various other conditions.	See BoilerStatus2 Flags in the Appendix for a list of flags and values.
nvoBlr01Status3 ... nvoBlr16Status3	SNVT_state 400 ... 415	Boiler status flags #3. These flags indicate the state of the stage control inputs.	See BoilerStatus3 Flags in the Appendix for a list of flags and values.
nvoBlr01Runtime ... nvoBlr16Runtime	SNVT_reg_val 500 ... 515	The total number of minutes that the boiler has been running (with the current control board).	0 – 35791394 minutes
nvoBlr01Cycles ... nvoBlr16Cycles	SNVT_reg_val 600 ... 615	The total number of boiler cycles (with the current control board).	0 – 2147483647 cycles
--- The following are supported in bridge configuration versions 2.20 and greater ---			
nvoBlr01Supply ... nvoBlr16Supply	SNVT_temp_p 616 ... 631	The boiler supply (outlet) temperature.	0 – 121.1 °C (32 – 250 °F)

KN2/KN4/rAy LonWorks Bridge Network Variables

v2.30

Name	SNVT Type/Index	Description	Valid Values/Range
nvoBlr01Return ... nvoBlr16Return	SNVT_temp_p 632 ... 647	The boiler return (inlet) temperature.	0 – 121.1 °C (32 – 250 °F)
--- The following are supported in bridge configurations 2.30 and greater --- (Control firmware version 2.70 or greater required)			
nvoBlr01Status4 ... nvoBlr16Status4	SNVT_state 648 ... 663	Boiler status flags #3. These flags indicate the state of various conditions.	See BoilerStatus4 Flags in the Appendix for a list of flags and values.
nvoBlr01DHW ... nvoBlr16DHW	SNVT_temp_p 664 ... 679	DHW Temperature.	0 – 121.1 °C (32 – 250 °F)
nvoBlr01Modulate ... nvoBlr16Modulate	SNVT_level_cont_f 680 ... 695	The running (“display”) modulation. This is typically the actual running modulation except under special circumstances when the boiler is running in a self-protection mode (Op. Limit, ½ Fire Rate, etc.)	0 – 100 %
nvoOpSetpoint	SNVT_temp_p 696	This is the current operating or active setpoint. It may be: 1) The normal heating setpoint. 2) The DHW setpoint if running in DHW mode. 3) A calculated setpoint if running in Outdoor Air Reset Mode 4) The 4-20ma (0-10V) setpoint.	4.5 – 104.4 °C (40 - 220 °F)

APPENDIX A – Status Flags

BoilerStatus1 Flags

Bit	Description	Valid Values/Range
0	Disabled Boiler is disabled.	0 = enabled, 1 = disabled
1	Local Override (member boilers only).	0 = no override, 1 = override
2	Alarm An alarm or warning condition has occurred. An attempt(s) will automatically be made to recover and resume normal operation.	0 = ok, 1 = alarm
3	Failed A condition has occurred under which the boiler can no longer run.	0 = ok, 1 = failed
4	Member Error An "Alarm" or "Failed" condition has occurred on one (or more) of the member boilers.	0 = ok, 1 = error
5	Boiler Running	0 = off, 1 = on (running)
6	Pump Running	0 = off, 1 = on (running)
7	---	---
8	---	---
9	---	---
10	---	---
11	Spare 4 (User) Interlock	0 = open, 1 = closed
12	---	---
13	Water Prove (Flow) Interlock	0 = not proven, 1 = proven
14	---	---
15	Main Valve	0 = closed, 1 = open

BoilerStatus2 Flags

Bit	Description	Valid Values/Range
0	---	---
1	Blower Running	0 = off, 1 = on (running)
2	Ignition Alarm	0 = ok, 1 = alarm
3	---	---
4	High Limit	0 = ok, 1 = tripped
5	---	---
6	---	---
7	Software Operator Tripped	0 = not tripped, 1 = tripped
8	Header Sensor not detected	0 = detected, 1 = not detected
9	Supply Sensor not detected	0 = detected, 1 = not detected
10	Return Sensor not detected	0 = detected, 1 = not detected
11	Outside Sensor not detected	0 = detected, 1 = not detected
12	---	---
13	Combustion Air Damper Prove.	0 = not proven, 1 = proven
14	Master Boiler	0 = member, 1 = master
15	Boiler Detected A boiler was detected at this address.	0 = not detected, 1 = detected

BoilerStatus3 Flags

Bit	Description	Valid Values/Range
0	AA High Fire Input	0 = off, 1 = on
1	Heat Demand Input (Local Override)	0 = off, 1 = on
2	4-20ma Remote Enable Input	0 = off, 1 = on
3	---	---
4	---	---
5	---	---
6	---	---
7	---	---
8	---	---
9	---	---
10	---	---
11	---	---
12	---	---
13	---	---
14	---	---
15	---	---

BoilerStatus4 Flags

Bit	Description	Valid Values/Range
0	DHW Sensor Enabled DHW Sensor has been enabled in the menus.	0 = off, 1 = on (menu)
1	Combustion Air Damper Prove.	0 = not proved, 1 = proven
2	---	---
3	Blower Fault	0 = ok, 1 = fault
4	Blocked Inlet	0 = off, 1 = fault
5	Blocked Flue	0 = ok, 1 = blocked
6	DHW Input	0 = off, 1 = on
7	Low Fire Input	0 = off, 1 = on
8	DHW Fault	0 = ok, 1 = fault
9	DHW Sensor not detected	0 = detected, 1 = not detected
10	---	---
11	Operating Limit Clamp Boiler input is being limited (clamped) due to a high supply (outlet) temperature.	0 = off, 1 = clamped
12	---	---
13	---	---
14	---	---
15	---	---